

15-051-22760-00-00

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,760

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Triple "H" Oil Operations, Attn: Irvin Haselhorst,

Complete Address 1011 Military Road, Hays, Kansas 67601

Lease Name Beath *Veach* Well No. #1

Location NW NW NW Sec. 4 Twp. 11 Rge. 20 (East)(West)

County Ellis Total Depth 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Dreiling Oil, Inc.

Address R. R. #1, Victoria, Ks. 67671 License No. _____

Operation Completed: Hour: 1:30PM Day: 16th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-263' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 840' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole and 5 sacks in mouse hole.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

INV

DATE

INV. NO.

STATE CORPORATION COMMISSION
RECEIVED
DEC 21 1981
W

