

15-051-22605-00-00

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22605 ✓ 16

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name K & E Petroleum, Inc.

Complete Address 100 So. Main, Suite #300, Wichita, Kansas 67202

Lease Name Fischer Well No. #1

Location 120' No. of Center-SW-NW Sec. 9 Twp. 11 Rge. 20 (East) West

County Ellis Total Depth 3624'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 8:15AM. Day: 12th Month: Oct. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

13 3/8" Conductor String-58' w/60 sacks common-2% Gel.-3% Cal. Cl.

8 5/8"-321' sp. cuc. w/185 sacks common-2% Gel-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem w/heavy mud between all plugs.

1st plug @ 840' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

STATE CORPORATION COMMISSION

10-19-1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

DATE: 11-23-81
8380-W