

3021630

TO:

API NUMBER 15- 001-27,164 -90-02

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION 3123 3465 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 1485 2475 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DIETRICH WELL # 25

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLENOPERATOR LICENSE # 5963WELL TOTAL DEPTH 897.5 FEETOPERATOR: WILLIS ENERGYPRODUCTION CSG: SIZE FEETNAME AND ROUTE 2, BOX 255SURFACE CASING: SIZE 7" FEET 20'ADDRESS NEODESHA, KS 66757ABANDONED OIL WELL GAS WELL INPUT WELL 29019.2 SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR FULLER OIL Co. TOOLS LICENSE NUMBER 31094 99998ADDRESS 1312 E. CARPENTER, IOLA, KS 66749COMPANY TO PLUG AT: HOUR: 12:30PM DAY: 8 MONTH: 4 YEAR: 99PLUGGING PROPOSAL RECEIVED FROM TAB SWITZER(COMPANY NAME) WILLIS ENERGY (PHONE) 316-325-5189

WERE: THIS WELL CONSISTED OF 2 7/8" CASING TO 897.5' THAT HAD BEEN CEMENTED IN FROM
BOTTOM TO TOP. THE 2 7/8" HAD BEEN PERFORATED FROM 849' TO 861'. THE PLUGGING
PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE XOPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 8 MONTH: 4 YEAR: 99

ACTUAL PLUGGING REPORT THE CEMENT PUMP WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING.
CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL
WAS THEN SHUT-IN AT 700 PSI. 21 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

KANSAS CORPORATION COMMISSION

FEB 25 2009

RECEIVED

REMARKS: THIS WELL IS DESCRIBED ON TA NO. 3-002,107.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-273

PBT