

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23565-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 26-16S-22W
349 feet from S Section Line, 2232 feet from E Section Line
Lease Name: UMMEL TRUST Well #: 1
County: NESS Total Vertical Depth: 4410 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1632		WITH 160 SX CMT TO SURFACE
PROD	5.5	4409	0	WITH 150 SX CMT
SURF	8.625	263		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: SAND OVER PERFS. PUMP 25 SX CMT & 200# HULLS. MUD TO 1650' THEN 25 SX CMT. MUD TO 1000'. CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF NEEDED.

143.33

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2009 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO CASING & PUMPED 35 SX CMT & 150# HULLS. PUMP 20 SX GEL WATER THEN 175 SX CMT. MAXIMUM PRESSURE 2000#. SHUT IN PRESSURE 1500#. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4302	4306		PERFORATED CHE

INVOICED

DATE 3-2-09
INV. NO. 2009061271

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

FEB 16 2009

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)