

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21248-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 4-17S-12W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WONDRA Well #: 2  
County: BARTON Total Vertical Depth: 3343 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3341	0	100 SX
SURF	8.625	215	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2009 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Perfed at 1500' - 750' - 175'.

108.65

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - tied to tubing - pumped 150 sxs cement with 300# hulls.  
Pulled tubing to 1500' - pumped 120 sxs cement with 100# hulls - circulated cement.  
Pulled tubing - tied to casing - pumped 55 sxs cement - circulated out backside.  
Shut in backside - squeezed to Max. P.S.I. 100#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3341	3343		OH

**INVOICED**  
DATE 3-2-09  
INV. NO. 2009061272

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 23 2009

Remarks: SWIFT SERVICES, INC.-TICKET #15447.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

FEB 20 2009

ACT

PETROLEUM ENERGY, INC.

710 125 BLDG.

WICHITA, KS.

CONTR B&G DRLG.

#2 WONDRA

CTY BARTON

GEOL

FIELD ODIN

E 1279 KB CM 10/14/77 CARD ISSUED 12/1/77 P 36 BOPD + 29 BWPD  
ARB 3341-43 OH

4-17-12W  
SE SW SE


API 15-059-21,248

LOG	TOPS	DEPTH	DATUM
HEEB		2977	-1098
TOR		2995	-1116
DOUG		3005	-1126
BR LM		3068	-1189
LANS		3086	-1207
ARB		3340	-1461
LTD		3343	-1464

8-5/8" 215/150sx, 4 1/2" 3341/100sx  
 DST (1) 3149-60/30-30-30-30, 5' OCM,  
 SIP 38-30#, FP 53-30#, 30-30#  
 DST (2) 3284-3300/30-30-30-30, 5' M,  
 ALL PRESSURES 20#  
 DST (3) 3334-43/30-30-30-30, 360' GO,  
 NW (GR 36°), SIP 909-939#, FP 76-  
 92#, 153-146#  
 MICT - CO TD, FU 600' OIL, N/W, AC 250  
 REC LD, SWB 2 1/2 BOPH, SD/ON FU 1200'  
 OIL + 800' W, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS