

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23462-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 4-17S-12W
4059 feet from S Section Line, 644 feet from E Section Line
Lease Name: LANG Well #: B-3
County: BARTON Total Vertical Depth: 3336 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3334	0	100 SX CMT
SURF	8.625	300	0	200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2009 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.
Perfed at 1400' - 660'.

108.42

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - tied to tubing - pumped 9 sxs gel - pumped 40 sxs cement with 100# hulls.
Pulled tubing to 1400' - pumped 40 sxs cement with 100# hulls.
Pulled tubing to 660' - pumped 90 sxs cement with 300# hulls - circulated cement to surface.
Tied to backside - pumped 25 sxs cement.
Max. P.S.I. 150#. Shut in.
Pulled tubing - topped off with 45 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3334	3336		

INVOICED
DATE 3-2-09
INV. NO. 2009001272

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 23 2009

Remarks: SWIFT SERVICES, INC.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

FEB 20 2009


PKT

BERGMAN OIL COMPANY
520 UNION CENTER #3-1 "B" LANG 4-17-12W
WICHITA, KS 67202 C E/2 E/2 NE

CONTR BERGMAN DRILLING, INC. CTY BARTON

GEOL _____ FIELD ODIN

ELV 1878 KB SPD 2/27/84 CARD ISSUED 6/21/84 IP P 25 BO & 100 BWPD
1873 GL ARB OH 3334-3335



SMP	Tops	Depth/Datum	API 15-009-23,462
			8 5/8 " 300 / 200SX, 4 1/2 " 3334/150SX
			DST (1) 3196-3254 (KC) / 20-15-15-15, REC 196' M, SIP 149-168#, FP 56-149#
			MICT - CO. (ARB OH), AC 500G (15%), SWB DWN, GSO, SET 2
			1/2 " TBG AT 3330', POP, P 25 BO & 100 BWPD, 5/10/84
HEEB	2950-1072	
IATAN LM	3060-1182	
LANS	3079-1201	
BKC	3318-1440	
CONG SD	3324-1446	
ARB	3332-1454	
RTD	3335-1457	

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS