

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Receipt per operator

API Well Number: 15-179-20557-00-00
Spot: SWNWESW Sec/Twnshp/Rge: 35-8S-27W
2300 feet from S Section Line, 3950 feet from E Section Line
Lease Name: GOETZ Kahle Well #: 1
County: SHERIDAN Total Vertical Depth: 4040 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4039	0	w/150 sxs cmt
SURF	8.625	298	0	w/298 sxs cmt

131.30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2009 3:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (620) 772-8649

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2009 8:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 298' w/250 sxs cement.
4 1/2" production casing set at 4039' w/150 sxs cement.
PBTD 3821'. TD 4040'.
02/17/2009 - Production casing perforated at 2225' - 1400' - 200'.
Ran tubing to 3970' - pumped 9 sxs gel - 50 sxs cement mixed with 150# hulls.
Pulled tubing to 2245' - circulated cement to surface with 100 sxs cement and 400# hulls.
Pulled tubing to surface.
Connected to production casing - pumped 55 sxs cement.
Max. P..S.I. 200#. S.I.P. 0#.
Cement circulated to surface from 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
3945	3951		
3923	3928		
3830	3834		
3788	3792		

INVOICED
DATE 3-2-09
INV. NO. 20090612 73

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #34953.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

PKT

