

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

*KCC PKT per spot research*

API Well Number: 15-179-20587-00-00  
Spot: W2NWSW Sec/Twnshp/Rge: 35-8S-27W  
2310 feet from S Section Line, 610 feet from W Section Line  
Lease Name: GOETZ KAHLE Well #: 2  
County: SHERIDAN Total Vertical Depth: 4060 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4058	0	w/175 sxs cmt
SURF	8.625	263	0	w/235 sxs cmt

*131.95*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2009 8:30 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (620) 772-8649

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/17/2009 1:00 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 263' w/235 sxs cement.  
4 1/2" production casing set at 4058' w/175 sxs cement.  
PBTD 4044'. TD 4060'.  
02/17/2009 - production casing perforated at 2275' - 1450' - 200'.  
Ran tubing to 3600' - pumped 9 sxs gel - 50 sxs cement mixed with 200# hulls.  
Pulled tubing to 2242' - circulated cement to surface with 130 sxs cement and 250# hulls.  
Pulled tubing to surface.  
Connected to production casing - pumped 55 sxs cement.  
Max. P.S.I. 400#. S.I.P. 200#.  
Cement circulated to surface from 8 5/8" surface casing.

**Perfs:**

Top	Bot	Thru	Comments
3996	4000		
3973	3980		

INVOICED

DATE 3-2-09

INV. NO. 2009061273

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 23 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #35024A.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN) CM

FEB 19 2009

*PKT*

TEXAS OIL & GAS CORP. 35-8-27W  
 200 W. DOUGLAS, #300 #2 GOETZ 2310' FSL & 610' FWL, SW/4  
 WICHITA, KS 67202  
 CONTR MURFIN DRG. CO. CTY. SHERIDAN

GEOL \_\_\_\_\_ FIELD JEROME

E 2661 KB CM 1/7/81 CARD ISSUED 3/5/81 IP P 60 BOPD & 4 BWPD  
 LANS 3973-4000 OA

+	+	+
+	+	+
+	+	+

API 15-179-20,587

LOG	TOPS	DEPTH	DATUM
TOP		3555	- 894
HEEB		3768	-1107
TOR		3792	-1131
LANS A		3808	-1147
LANS B		3837	-1176
LANS H		3930	-1269
LANS J		3972	-1311
LANS K		3993	-1332
B KC		4027	-1366
TD		4060	-1399
PBTD		4044	-1383

8-5/8" 263/235SX, 4 1/2" 4058/175  
 DST (1) 3769-3822/30-60-30-60, REC 3'  
 SOCM, SIP 675-675#, FP 39-39/39-39#  
 DST (2) 3827-3843/30-60-45-90, REC 62'  
 OCM, SIP 212-212#, FP 55-63/102-110#  
 DST (3) 3851-3910/30-60-45-90, REC 1674'  
 MGCW, SIP 943-951#, FP 196-566/676-770  
 DST (4) 3950-3983/30-60-45-90, REC 240'  
 GO & 210' HO & GCM, SIP 353-275#, FP 31-39/94-110#  
 MICT - CO, AC 250 GAL, PF (LANS J), 14/3973-3980 & (LANS K), 8/3996-4000,  
 SWB 1 1/2 BFPH (100% OIL)/4 HRS, AC 4000G,  
 SWB BACK 7.5 BFPH (80% OIL)/2HRS,  
 POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS