

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23532-00-00  
Spot: W2SESWSW Sec/Twnshp/Rge: 15-8S-21W  
330 feet from S Section Line, 750 feet from W Section Line  
Lease Name: SWAYNE Well #: 1  
County: GRAHAM Total Vertical Depth: 3570 feet

Operator License No.: 33306  
Op Name: BLAKE EXPLORATION, LLC  
Address: 201 S MAIN PO BOX 150  
BOGUE, KS 67625

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 211

116.03

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2009 6:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: BLAKE EXPLORATION, LLC Phone: (785) 421-2921

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 02/16/2009 8:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 1593' w/25 sxs.  
2nd. Plug at 923' w/100 sxs.  
3rd. Plug at 260' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

INVOICED  
DATE 3-2-09  
INV. NO. 2009061274

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 23 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

FEB 19 2009

PKT