

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03613-00-00  
Spot: SWNW Sec/Twnshp/Rge: 31-11S-17W  
3257 feet from S Section Line, 4704 feet from E Section Line  
Lease Name: MARSHALL A Well #: 13  
County: ELLIS Total Vertical Depth: 4201 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3757	0	1600 SX
SURF	8.625	1355	0	350 SX

136.53

Well Type: SWD UIC Docket No: D00747.0 Date/Time to Plug: 02/19/2009 9:00 AM  
Plug Co. License No.: 5214 Plug Co. Name: LARIO OIL & GAS COMPANY  
Proposal Rcvd. from: DAVID L. JENSEN Company: LARIO OIL & GAS COMPANY Phone: (785) 625-5023

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.  
Perfed 3657'-3663' cemented with 300 sxs; 2069' cemented with 300 sxs; 1759' cemented with 300 sxs.  
Junk in the hole - estimated 17 joints of 3 1/2" and other junk - estimated top 3069'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/19/2009 11:40 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

8 5/8" full on backside - visual check.  
Lario RIH with tubing to 2980'. Allied rigged to tubing - pumped 9 sxs gel - followed with 35 sxs 60/40 pozmix - 4% gel neat followed with 40 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.  
Pulled tubing to 2035'. Allied rigged to tubing - pumped 180 sxs 60/40 pozmix - 4% gel with 350# hulls to circulate cement to steel tank.  
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 25 sxs cement.  
Max. P.S.I. 300#. S.I.P. 200#.

**Perfs:**

**INVOICED**  
DATE 3-2-09  
INV. NO. 2009061281

KANSAS CORPORATION COMMISSION


**FEB 25 2009**  
**RECEIVED**

Remarks: ALLIED CEMENTING COMPANY-TICKET #34893.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3


**FEB 20 2009**

*PKT*

LARIO OIL & GAS CO #13 MARSHALL 31-11-17W  
 C SW NW  
 Contr. \_\_\_\_\_ ELLIS County  
 E 2108 Comm. 9-16-42 Comp. 11-18-42 IP S W D W

Tops	Depth	Datum
ANH	1344	
LANS	3350	
B/KC	3603	
CONG	3604	
SIMP	3646	
ARB	3655	
PRE CAM	4136	
TD	4201	

Casing  
 8" 1355  
 5" 3757  
 Cored 3657-60,  
 3660-65  
 SSO: 150' mud; VSSO: Perf  
 3859-62: 330 BWPB



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

0101 1101 - 111