

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20319-00-00
Spot: E2SESWNW Sec/Twnshp/Rge: 24-31S-32W
2970 feet from S Section Line, 1250 feet from W Section Line
Lease Name: COVEL TRUST UNIT Well #: 1
County: SEWARD Total Vertical Depth: 2691 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2690	730	WITH 550 SX CMT
SURF	8.625	575		

87.46

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/28/2009 1:00 PM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 2600' & 2 SX CMT OR PUMP 200# HULLS & 25 SX CMT. 1ST PLUG TOP OF CASING FREE POINT LOAD HOLE WITH GEL WATER & PUMP 50 SX CMT. 2ND PLUG CIRCULATE CMT FROM 600-0'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2009 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT INTO PERF AT 2655'. PUMP 205 SX CMT AT 730'. FILLED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2655	2665		KRIDER

INVOICED
DATE 3-2-09
INV. NO. 2009061283

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

FEB - 6 2009

KCC DODGE CITY

PKT