

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21643-00-01
Spot: SWNENENW Sec/Twnshp/Rge: 14-33S-32W
4806 feet from S Section Line, 3217 feet from E Section Line
Lease Name: ALEXANDER Well #: 2-14
County: SEWARD Total Vertical Depth: 3130 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2722		WITH 2 SX CMT
PROD	5.5	3129	630	WITH 175 SX CMT
SURF	8.625	602		WITH 250 SX CMT

Well Type: SWD UIC Docket No: D27494.0 Date/Time to Plug: 02/03/2009 10:00 AM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WATERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 2890' & 2 SX CMT. CIBP @ 2650' & 2 SX CMT OR 200# HULLS & 35 SX CMT. 50 SX CMT ON TOP OF CASING AT FREE POINT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40'-0' WITH 10 SX CMT.

101.73

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 2722' WITH 2 SX CMT. PUMP 200# HULLS & 35 SX CMT AT 2640'. 1ST PLUG AT 630' WITH 50 SX CMT. 2ND PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3028	3035		COUNCIL GROVE
2991	3002		COUNCIL GROVE
2885	2902		COUNCIL GROVE
2682	2692		LOWER KRIDER
2640	2652		UPPER KRIDER

INVOICED

DATE 3-2-09
INV. NO. 2009061283

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

MP

RECEIVED

FEB - 6 2009

KCC DODGE CITY

Signed

Jack MacLashy
(TECHNICIAN)

Form CP-250

PT