

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21776-00-00
Spot: N2NW Sec/Twnshp/Rge: 22-33S-31W
4620 feet from S Section Line, 3960 feet from E Section Line
Lease Name: THORP B Well #: 1
County: SEWARD Total Vertical Depth: 2800 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2799	0	WITH 400 SX CMT
SURF	8.625	556		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/29/2009 9:00 AM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (316) 682-3022

Proposed Plugging Method: RIHT TO 1400'. PUMP 100# HULLS & 25 SX CMT. PULL TO 600'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE TO 500 PSI.

91.00

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2009 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RODS PARTED @ 1525'. LEFT IN HOLE. TBG PARTED @ 1461 PUMP 100# HULLS & 25 SX CMT AT 1400'. TBG IN HOLE @ 600'. PUMPED 400 SX CMT THROUGH TBG. NO CIRCULATION INSIDE 4 1/2" WITH 120 SX CMT IN, 4 1/2" X 8 5/8" ANNULUS STARTED CIRCULATING CLEAR WATER, TURNED INTO IRON SULFATE WATER AT END OF PUMPING. NO CMT. SET 1 1/2 HOUR & PUMPED 125 SX CMT DOWN 4 1/2". NO FILLING OR CIRCULATION AT CASING ANNULUS. SLIGHT BLOW. SDON. 1/30/09: TAGGED CMT AT 380'. PUMPED 50 SX CMT DOWN CASING ANNULUS & PRESSURED TO 500#. RIH W/TBG TO 370'. PUMPED 23 SX CMT. FILLED 4 1/2"

Perfs:

Top	Bot	Thru	Comments
2699	2705		WINFIELD (SQUEE)
2637	2660		LOWER KRIDER
2601	2616		KRIDER
2568	2577		HERINGTON

INVOICED
DATE 3-2-09
INV. NO. 2009061283

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
FEB - 6 2009

Signed

Jack MacLashy
(TECHNICIAN)

KCC DODGE CITY

[Signature]