

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20882-00-00
Spot: NENWNW Sec/Twnshp/Rge: 26-34S-16W
330 feet from N Section Line, 1250 feet from W Section Line
Lease Name: HUCK Well #: 1-26
County: COMANCHE Total Vertical Depth: 5300 feet

Operator License No.: 33355
Op Name: S & C CONSTRUCTION, INC.
Address: PO BOX 1509
WHITEFISH, MT 59937

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5300	3020	WITH 200 SX CMT
SURF	8.625	828		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2009 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: STEVE COSBY Company: S & C CONSTRUCTION Phone: (406) 862-2690

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 850' WITH 12 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

172.25

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2009 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT. TAGGED CMT AT 4490'. 1ST PLUG AT 850' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 50# HULLS & 40 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED

Perfs:

Top	Bot	Thru	Comments
5054	5068		
4945	4949		
4607	4610		

INVOICED
DATE 3-2-09
INV. NO. 2009061287

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED

FEB 19 2009

KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-2/3

[Handwritten signature]