

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: SCOTT'S WELL SERVICE
Address: BOX 136, ROXBURY, KS 67476
Phone: (785) 254-7828 Operator License #: 6819
Type of Well: SWD Docket #: D- E21490
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/11/2009 (Date)
by: GREG EAVES (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MAQUOKETA Depth to Top: 3220 Bottom: 3224 T.D. 3224
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - Drilling Completed 8/17/1960
Lease Name: STAHL
Well Number: 1
Spot Location (QQQQ): NE SW - NE - NW
660 4611 Feet from North / South Section Line
1650 3342 Feet from East / West Section Line
Sec. 5 Twp. 15 S. R. 2 East West
County: SALINE
Date Well Completed: 4/14/1960
Plugging Commenced: 2/12/2009
Plugging Completed: 2/12/2009

169-00445-00-01

KCC DISTRICT AGENTS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MAQUOKETA	Dolomite	3220	3224	4-1/2	3220	NONE
	Surface	0	171	8-5/8	171	NONE
	Fiberglass Tubing	0	2911	2-3/8	2911	420'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Ran 2-3/8 tubing and packer to 360'. Set packer and pumped 80 sacks cement down well. Pulled tubing and packer. Ran 1" pipe to 290'. Tagged cement. Pumped 125 sacks cement. Circulated to surface. Pulled pipe. Ran 2-3/8 tubing to 360' inside 4-1/2 casing. Pumped 40 sacks cement down tubing. Circulated to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 19 2009
CONSERVATION DIVISION
WICHITA, KS

Name of Plugging Contractor: Scott's Well Service Inc License #: 6819
Address: PO Box 136, Roxbury, KS 67476
Name of Party Responsible for Plugging Fees: Scott's Well Service
State of Kansas County, McPherson, ss.
Jay Scott

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay Scott
(Address) Box 136, Roxbury, KS 67476



SUBSCRIBED and SWORN TO before me this 18th day of February, 2009
Julie A. Karber My Commission Expires: 8/13/2012
Notary Public

PKT