

15-195-20649-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER spud 6/13/80

LEASE NAME Buchholz B

WELL NUMBER #1

990 Ft. from S Section Line

2970 Ft. from ^W Section Line

SEC. 7 TWP. 11 RGE. 22 (E) or (W)

COUNTY Trego

Date Well Completed 8/5/80

Plugging Commenced 4/28/99

Plugging Completed 4/28/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188, Wichita, KS 67278

PHONE#(316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 23, 1999 (date)

by Roger Moses (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation LKC-Marmaton-Arb Depth to Top 3539 Bottom 3911 T.D. 3921 (PBSD)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil & brine	surface	191	8 5/8	6/80	none
LKC	oil & brine	surface	393	1 4 1/2	6/21/80	none
Marmaton	oil & brine					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf @ 2175 & 1735 2 SPF. TIH with 2" tbg to 2900'FS, mix & pump 100 sacks
60/40 poz mix 10% gel & 400# hulls. Move tbg up hole to 1500'FS, circ cut to
surface using 140 sacks 60/40 poz 10% gel with 400# hulls. Ion with tbg top off
& squeeze 4/1/2 csg with 30 sacks 60/40 poz 10% gel. Max psi 700#, ISIP 400#
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service, Inc. License No. 6426

Address 1110 Hwy 40, Victoria, KS 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

David F. Jamis

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: ~~That I have knowledge of the facts,~~ statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David F. Jamis

(Address) P.O. Box 783188, Wic., KS 67278

STATE OF KANSAS NOTARIES PUBLIC AND SWORN TO before me this 27th day of May, 19 99



Andrea Perez

Notary Public
Andrea Perez

My Commission Expires: January 26, 2002
Wichita, Kansas

Cement was visible at surface in anaulus (from squeeze that circ)