

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Trego SEC. 6 TWP. 11s RGE. 22w E/W
Location as in quarters or footage from lines:
(440' loc.) SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Don E. Pratt Oil Operations
Lease Name McCall #1 Well No. _____
Office Address P.O. Box 370, Hays, Ks. 67601
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/31/83
Plugging completed 6/2/83
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation _____ Depth to top _____ bottom T.D. 4020'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	181'	none
				4 1/2"	4017'	2709'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with 4 sacks cement, sand back to 3875' & 4 sacks cement.
Shot pipe at 3011', 2835', & 2707'. Pulled 63 joints. Plugged well with
2 hulls, 30 gel, 100 cement, 10 gel, Released plug & displaced with 70 cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June, 19 83

My Commission expires: 

STATE CORPORATION COMMISSION

JUN 09 1983
6-9-1983
CONSERVATION DIVISION
Wichita, Kansas

15-195-21002-00-00

WELL LOG

COMPANY Don Pratt

SEC. 6 T11S R. 22W
LOC. (440' loc) SW SW

FARM McCall NO. 1


RIG. NO. 21

TOTAL DEPTH 4020'

COUNTY Trego KANSAS

COMM. 6-15-82

COMP. 6-23-82



CONTRACTOR Murfin Drilling Company

CASING

20 10
15 8-5/8" csg set @ 181' w/165 sx., Common Quickset ELEVATION

12 6
13 5
4 1/2" csg set @ 4017' w/200 sx, Common, 8% salt, 2% CC PRODUCTION
FIGURES INDICATE BOTTOM OF FORMATIONS


Soil & Sand 70'
Shale 2930'
Shale & Lime 3955'
Lime 4020'

RECEIVED
STATE CORPORATION COMMISSION
4-22-1983
APR 22 1983
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK ss:

I, David L. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the McCall #1 well.



David L. Murfin
David L. Murfin

Subscribed and sworn to before me this 6th day of July 1982

My Commission Expires: 1-25-84

Ramona Gunn
Ramona Gunn NOTARY PUBLIC