

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-195-00016-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County. Sec. 7 Twp. 11 Rge. 22 (E) W (W)
Location as "NE/CNW&SW" or footage from lines. NW/4 NW/4 NE/4
Lease Owner Prime Drilling Company & Davis Bros.
Lease Name Kircheck Well No. 1
Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-8-1952
Application for plugging filed 7-12-1952
Application for plugging approved 7-12-1952
Plugging commenced 7-12-1952
Plugging completed 7-12-1952
Reason for abandonment of well or producing formation _____

NORTH

		X	

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3943 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	217	None
				5-1/2	3943	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3524 to 3490 Sand Bridge
3490 to 3460 5 Sacks Cement
3460 to 255 Mudded
255 to 240 Rock Bridge
240 to 200 15 Sacks Cement
200 to 35 Mudded
25 to Cellar 10 Sacks Cement

RECEIVED
STATE CORPORATION COMMISSION
7-17-1952
JUL 17 1952
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & S Pipe Pulling Co.
Address Ellinwood, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. J. Kruse*
Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1952

My commission expires October 24, 1955 Notary Public.

24-2675-S 2-52-20M
PLUGGING
FILED 7-16-1952
PAGE 29 LINE 4V

15-195-00016-00-00

PRIME DRILLING COMPANY & DAVIS LOGS.

NW/4 NW/4 NE/4 Sec. 7-11S-22E
Trego County, Kansas

KIRCHECK NO. 1

<u>FORMATIONS</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Sand	0	10	
Sand	10	45	
Clay Shale	45	120	5-5/8" C.S.A. @ 195'. Cemented
Shale	120	630	with 125 sacks cement.
Shale Sand Pyrite	630	810	
Pyrite & Sand	810	880	
Sand Shale & Shells	880	990	
Sand	990	1080	
Red Bed Shale & Shells	1080	1150	
Sand & Shale	1150	1260	
Shale Shell Red Bed	1260	1695	
Anhydrite	1695	1740	
Red Bed Shale & Shells	1740	2005	
Shale Shells Red Bed	2005	2205	
Shale & Lime	2205	3515	
Lime	3515	3750	
Lime & Shale	3750	3826	
Chert	3826	3845	
Shale Lime & Chert	3845	3931	5-1/2" C.S.A. @ 3922'. Cemented
Lime	3931	3943	with 100 sacks cement.
Total Depth		3943'	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

PRIME DRILLING COMPANY

By: L. J. Kruse
L. J. Kruse, Secretary

Subscribed and sworn to before me this 28th day of May, 1952.

William H. ...
Notary Public

My Commission Expires:

October 24, 1955.

7-17-1952

7-11-220
29 4