

15-195-21532-00-00

4-110094

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-195-21,532-00-00

NE SE SE /4 SEC. 24, 11 S, 21 W  
990 feet from S section line  
330 feet from E section line

Operator license# 100

Lease: Hall Well # 1-24

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #20000023-001

County: Trego  
Well total depth 3940 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 210 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kansas Coporation Commission License# 100

Address: 2301 E. 13<sup>th</sup> Street - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 21 Month: April Year: 2000

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Ordered 230 sxs and 400# hulls.  
Plug thru tubing.

RECEIVED  
STATE CORPORATION COMMISSION  
5-12-2000  
MAY 12 2000

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

CONSERVATION DIVISION  
Wichita, Kansas

Completed: Hour: 12:45 P.M., Day: 21, Month: April, Year: 2000

Actual plugging report: 8 5/8" S.P. set at 210' w/180 sxs. 4 1/2" casing at 3898' w/175 sxs. 360 sxs cement 975' to surface. R.I.H. with tubing to 1240' and spotted 30 sxs cement. Pulled tubing to 700' and circulated with 50 sxs cement. Pulled all tubing. - tied to 4 1/2" casing - pumped 110 sxs cement to Max. P.S.I. 800#. S.I.P. 500#. Tied to 4 1/2" x 8 5/8" annulus - pressured to Max. P.S.I. 600#. Took no cement. Total of 190 sxs 60/40 pozmix.

Remarks: Allied Cementing. Fischer Well Service - Werth Tank.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: 2290 GL

I did [ X ] / did not [ ] observe the plugging.

Raymond M... (agent)  
Form CP-2/3  
R

