

15-195-22201-00-00

x

Corrected Copy

4-061228

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-22,201-0000
105'S. & 110'E. of
W2 NW NW /4 SEC. 35, 11 S, 21 W
4515 feet from S section line
4840 feet from E section line

Operator license# 32322

Lease: Bodine Well # 1

Operator: Denis F. Roberts

County: Trego

Address: 3904 Fairway Drive
Hays, Kansas 67601

Well total depth 4003 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Discovery Drilling Company License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 30 Month: May Year: 2000

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: _____

Were: Order 225 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 3:30 P.M., Day: 30, Month: May, Year: 2000

Actual plugging report: Article

KANSAS CORPORATION COMMISSION

- 1st. Plug at 3940' w/25 sxs cement. ~~Anhydrite~~ Top at 3949'.
- 2nd. Plug at 1760' w/25 sxs cement. Anhydrite 1731' - 1762'.
- 3rd. Plug at 1000' w/100 sxs cement. Dakota 693' - 993'.
- 4th. Plug at 265' w/40 sxs cement. Surface pipe to 212'.
- 5th. Plug at 40' w/10 sxs cement.

AUG 17 2000
8-17-2000

CONSERVATION DIVISION
WICHITA, KS

Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD X BAD _____
Bottom plug (in place): YES _____, CALC _____, NO _____
Plugged through TUBING _____, CASING _____. Elevation: 2293 GL

I did[] / did not[X] observe the plugging.

[Signature]
DH (agent)