

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21442-00-00
Spot: E2SWNWNE Sec/Twnshp/Rge: 27-34S-16W
990 feet from N Section Line, 2080 feet from E Section Line
Lease Name: HUCK Well #: 1-27A 5638
County: COMANCHE Total Vertical Depth: 6210 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5099	3740	WITH 215 SX CMT
SURF	8.625	1152		WITH 500 SX CMT

183.24

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/11/2009 9:57 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS Phone: (316) 682-3022

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2009 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT. TOC @ 4320'. 1ST PLUG AT 1170' WITH 100# HULLS, 15 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 100# HULLS & 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED BUT WELL WAS TAKING FLUID. 2/12/09: TOPPED OFF WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4965	4971		
4806	4820		
4800	4803		
4759	4761		SWOPE
4430	4440		LANSING B

INVOICED
DATE 2-25-09
INV. NO. 2009061264

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 19 2009
CONSERVATION DIVISION
WICHITA KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
FEB 13 2009
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form SP-2/3

PKT