

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21451-00-00
Spot: SWSE Sec/Twnshp/Rge: 35-29S-35W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MERRITT MLP Well #: 2-35
County: GRANT Total Vertical Depth: 5700 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		3034		
PROD	4.5	5697	2120	WITH 125 SX CMT 185.25
SURF	8.625	1824		WITH 545 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2009 9:00 AM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 5500'. 50 SX CMT AT STUB. PLUG AT 1840' WITH 50 SX CMT. PLUG AT 660-0'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2009 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS @ 5505'. 1ST PLUG AT 3053' WITH 25 SX CMT. NO CIRCULATION. 2ND PLUG AT 1850' WITH 50 SX CMT. NO CIRCULATION. 3RD PLUG PULL TO 660' & LOAD HOLE. WAS ALMOST FULL. PUMP 170 SX CMT & CIRCULATE HOLE FULL OF CMT IN 2 STAGES.

Perfs:

Top	Bot	Thru	Comments
5590	5594		BASAL CHESTER

INVOICED
DATE 2-25-09
INV. NO 20090661264

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 19 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED

JAN 16 2009

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CP-2/3

[Signature]