

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20814-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 4-24S-12W  
990 feet from S Section Line, 990 feet from W Section Line  
Lease Name: KELLY Well #: 1  
County: STAFFORD Total Vertical Depth: 3845 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3924	1918	WITH 100 SX CMT
SURF	8.625	275		WITH 250 SX CMT

124.94

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2009 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3700' & 4 SX CMT. PLUG AT 700' WITH GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/12/2009 3:01 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*CASING SQUEEZED @2570-2785\*\* SANDED TO 3700' & 4 SX CMT. 1ST PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3759	3765		
3751	3753		
2570	2785		

INVOICED  
DATE 2-25-09  
INV. NO. 2009061267

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 19 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
FEB 13 2009  
KCC DODGE CITY

Comp C 2/3  
PKT