

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20582-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 11-18S-43W  
760 feet from S Section Line, 2080 feet from E Section Line  
Lease Name: HUDDLESTON Well #: 34-11  
County: GREELEY Total Vertical Depth: 5300 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments               |
|--------|-------|------------|-------------|------------------------|
| DVT    |       | 2013       |             | WITH 500 SX CMT        |
| PROD   | 5.5   | 5297       | 0           | WITH 800 SX CMT 172.25 |
| SURF   | 8.625 | 239        |             | WITH 175 SX CMT        |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2009 11:00 AM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: BRETT HILDEBRAND Company: VESS OIL Phone: (785) 871-7311

Proposed Plugging Method: CIBP 50' ABOVE PERFS & 2 SX CMT OR 25 SX CMT & 200# HULLS. PLUG AT 2013' WITH 25 SX CMT. PLUG AT 1650-0'. CHECK ANNULUS

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/03/2009 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT & 250# HULLS AT 4705'. CIRCULATE 5 1/2" CASING FULL OF CMT FROM 2017-0' THROUGH TBG USING 200 SX CMT. FULL RETURNS. TOOH W/TBG. ATTEMPT TO TOP OFF. PUMP 135 SX CMT W/HULLS. WOULD NOT FILL. PUMP 20 SX CMT DOWN THE ANNULUS. PRESSURE TO 200 PSI. 2/2/09: TAG TOC @ 300' IN 5 1/2" CASING. 2/3/09: FILL 5 1/2" CASING WITH 1 1/2 YARDS REDIMIX FROM 300'-0'. U

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5153 | 5188 |      |          |

INVOICED

DATE 2-29-09

INV. NO. 2009001263

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 19 2009

CONSERVATION DIVISION  
WICHITA, KS


Remarks: USED 60/40 POZMIX 4% GEL BY SCHIPPERS OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
FEB - 9 2009  
KCC DODGE CITY

Signed



(TECHNICIAN)

Fohn 2/23  
PBT