

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20590-00-00
Spot: SENENW Sec/Twnshp/Rge: 11-18S-43W
810 feet from N Section Line, 3150 feet from E Section Line
Lease Name: HGB BREWER Well #: 2
County: GREELEY Total Vertical Depth: 5250 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2442		WITH 500 SX CMT
PROD	5.5	5249	0	WITH 150 SX CMT
SURF	8.625	351		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2009 10:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: BRETT HILDEBRAND Company: VESS OIL Phone: (785) 871-7311

Proposed Plugging Method: CIBP & 2 SX CMT 50' ABOVE PERFS OR PUMP 200# HULLS & 25 SX CMT. 25 SX CMT AT DV TOOL. PLUG AT 1650'-0'. CHECK ANNULUS.

170.63

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2009 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT & 200# HULLS @ 4970'. NO CIRCULATION. PUMP 25 SX CMT AT 2475'. NO CIRCULATION. PUMP 225 SX CMT AT 1650'. PARTIAL CIRCULATION. ON VACUUM AFTER SHUT DOWN. 1/30/09: TAG TOC @ 1412'. FL @ 800'. CIRCULATE CMT FROM 1392-0' WITH 140 SX CMT. TOOH W/TBG & TOP WELL OFF WITH 10 SX CMT. PUMP 25 SX CMT DOWN ANNULUS. PRESSURE TO 200# & HELD.

Perfs:

Top	Bot	Thru	Comments
5152	5157		
5146	5148		

INVOICED

DATE 2-25-09

INV. NO. 2009061263

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 19 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SCHIPPERS OILFIELD SERVICES.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED

FEB - 9 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

Four CD 2/3

