

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05988-00-00
Spot: S2N2SW Sec/Twnshp/Rge: 19-12S-15W
1650 feet from S Section Line, 3960 feet from E Section Line
Lease Name: RUSCH B Well #: 4
County: RUSSELL Total Vertical Depth: 3302 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3300	0	w/unknown sxs cmt
SURF	8.625	953	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2009 11:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.
Perf 1600'.

107.32

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2009 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2998' - pumped 40 sxs cement - 3% c.c.
Pulled tubing up 2600'.
Ran tubing back to 2998' - pumped 11 sxs gel - 40 sxs cement with 100# hulls.
Pulled tubing to 1612' - pumped 80 sxs cement with 200# hulls.
Pulled tubing to 808' - pumped 80 sxs cement with 200# hulls - cement circulated.
Pulled tubing out of well - topped off with 10 sxs cement.
Hooked up to backside - pumped 10 sxs cement.
Max. P.S.I. 500#.

Perfs:

INVOICED
DATE 2-25-09
INV. NO. 2009061263

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34889.

Plugged through: TBG

District: 04

Signed Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

FEB 13 2009

987

SOHIO PETROLEUM COMPANY

#4 RUSCH 'B'

19-12-15W
S2 N2 SW 33

Contr. BENNETT & ROBERTS

RUSSELL County

E 1893RB Comm 5-1-58

Comp. 6-6-58

IP

100 BOPD

Tops	Depth	Datum
ANH	942	951
TOP	2710	-847
HEEB	2958	-1065
TOR	2980	-1087
LANS	3012	-1119
B/KC	3275	-1382
REAG	3292	-1399
GR WSH	3294	-1401
TD	3302	-1409

Casing

8" 752

5" 3300

PERF 2740-3245: ACID 9500

FAIRPORT POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS