

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19288-00-00
Spot: NENESW Sec/Twnshp/Rge: 19-12S-15W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RUSCH B Well #: 2
County: RUSSELL Total Vertical Depth: 3352 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| PROD | 7 | 3230 | 0 | w/unknown sxs cmt |
| SURF | 10.75 | 956 | 0 | w/unknown sxs cmt |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2009 1:00 PM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed 02/05/2009 - Ordered 375 sxs 60/40 pozmix - 4% gel - 800# hulls.
Plugging 02/06/2009 - Ordered 450 sxs 60/40 pozmix - 4% gel - 800# hulls - 15 sxs gel.
Method: 02/09/2009 - Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 150 sxs ASC Cement.
Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1600'.

108.94

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2009 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

02/05/2009 - Tubing at 3075' - pumped 15 sxs gel and 60 sxs cement with 200# hulls.
Pulled tubing to 1917' - pumped 150 sxs cement with 400# hulls.
Pulled tubing to 975' - pumped 165 sxs cement with 200# hulls - well on strong vacuum.
02/06/2009 - Tagged at 1440' - pumped 160 sxs cement with 400# hulls - well on vacuum.
Pumped 30 sxs cement with 200# hulls.
Pumped 90 sxs cement with 400# hulls.
Pumped 150 BBL's of drilling mud - followed with 170 sxs cement.
02/09/2009 - Tagged TOC 1210' - pumped 280 sxs cement with 450# hulls.
Pulled tubing - tagged TOC 605' - pumped 70 sxs cement with 50# hulls.
Pulled tubing out - pumped 75 sxs ASC cement with 400# hulls.
Pumped 75 sxs ASC cement with 150# hulls.
Pumped 65 sxs cement - filled casing - 10 sxs on backside.
Max. P.S.I. 150#.

INVOICED
DATE 2-25-09
INV. NO. 2009061263

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #035020A-0350201A-0350202A.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

FEB 16 2009

PKT

SOHIO PETROLEUM CO

#2

RUSCH B

33

19-12-15W
NE NE SW

Contr.

RUSSELL

County

E. 1902

Comm.

Comp.


4-2-48

IP 50 BOPD

| Tops | Depth | Datum |
|------|-------|---------|
| | | |
| LANS | 3016 | -1114 ✓ |
| | | |
| CONG | 3304 | -1402 |
| | | |
| T.D. | 3352 | -1450 |

Casing
6" 3016

OLD WELL DD
 OLD TD 3136
 DD 3352
 2100' WTR/1 HR
 PLUG 3230
 PERF 3195-3205
 ACID 1000
 4 1/2 BOPH & 1 1/2 BWPH/3HRS.



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS