

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23529-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 21-12S-20W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BITTEL Well #: 1-B
County: ELLIS Total Vertical Depth: 3990 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3987	0	w/375 sxs cmt
SURF	8.625	896	0	w/375 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2009 9:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Pulled rods and 1/2 of pump. Tubing stuck.

Control # 20080062001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2009 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tubing parted at 6' down from surface.
Pert Tech perforated inside of tubing at 2200' - 1700' - 800'.
Allied pumped 200 sxs 60/40 pozmix - 4% gel neat - followed with 45 sxs cement with 150# hulls.
Max. P.S.I. 700#. S.I.P. 500#.
Hooked up to 8 5/8" - pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Note: Tubing parted 6' from surface depth unknown.

Perfs:

Top	Bot	Thru	Comments
3908	3916		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 17 2009

Remarks: ALLIED CEMENTING COMPANY.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

FEB 10 2009

N-B COMPANY, INC.
P.O. BOX 506
RUSSELL, KS 67665

#1 "B" BITTEL


21-12-20W
NW NW NE

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL _____ FIELD DIST 57 NO. EXT
(1/8 E)

ELV 2294 KB SPD 7/6/83 CARD ISSUED 9/8/83 IP P 25 BOPD, NW
MARM 3908-3916

API 15-051-23,529



SMP	Tops	Depth Datum
ANH	1660 634
TOP	3342-1048
HEEB	3572-1278
TOR	3593-1299
LANS	3611-1317
BKC	3856-1562
MARM	3904-1610
CONG	3956-1662
RTD	3990-1696

8 5/8 " 896 / 375SX; 4 1/2 " 3987 / 375SX
NO DSTS
MICT - CO. PF (MARM) 3908-3916. W : 2 SPF, AC 500G. FRAC
W/NITRO & 37,000# SD, SWB LD, T&R, POP, P 25 BOPD, 7'30'
83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

NOTE: CORRECTION: 7/21/83 - ORIGINALLY FIRST REPORTED AS
#1 "A" BITTEL