

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22857-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 21-12S-20W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BITTEL Well #: 3
County: ELLIS Total Vertical Depth: 3925 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3924	0	w/100 sxs cmt
SURF	8.625	809	0	w/350 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2009 2:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls.
Low fluid level.

Control # 20080062003

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2009 4:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 775'.
Allied rigged to casing - pumped 300 sxs 60/40 pozmix - 4% gel with 450# hulls mixed in.
Max. P.S.I. 900#. S.I.P. 300#.
Rigged to 8 5/8" casing - pumped 50 sxs cement.
Max. P.S.I. 400#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3832	3839		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 17 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #033625.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 04

Signed

[Signature]

(TECHNICIAN)

CM

FEB 11 2009

Form CP-2/3

[Signature]

N-B CO., INC. #3 BITTEL 21-12-20W
 P.O. BOX 506 NW NW NW
 RUSSELL, KS 67665-0506
 CONTR EMPHASIS OIL OPER. CTY ELLIS
 GEOL _____ FIELD DIST. 57 NORTH
 E 2223 KB CM 2/9/82 CARD ISSUED 4/29/82 IP P 25 BOPD
 API 15-051-22,857 MARM 3832-3839

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3488	-1265
TOR		3508	-1285
LANS		3525	-1302
BKC		3767	-1544
MARM		3820	-1597
PENN CONG		3854	-1631
ARB		3906	-1683
TD		3925	-1702

8-5/8" 809/350sx, 5 1/2" 3924/100sx
 DST (1) 3822-27/30-45, REC 60' VSOCM,
 260' M, ISIP 296-FS IP NA, FP 201-
 201#, HP 2021-2010#
 MICT - CO, PF 14/3832-39, AC 1000G,
 FRAC 15,000GAW & 15,000#SO, SWB 14
 BFPH, 65% O/B HRS, R&T, POP, P 25
 BOPD, NW, 3/3/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS