

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23076-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 21-12S-20W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BITTEL Well #: 4  
County: ELLIS Total Vertical Depth: 3930 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3926	0	w/150 sxs cmt
SURF	8.625	800	0	w/400 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2009 10:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 800# hulls - 10 sxs gel.  
No squeeze records: Perforate at 2200' - 1625' - 775'.

Control # 20080062004

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2009 8:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated two holes each at 2200' - 1625' - 775'.  
Ran tubing to 3600'. Allied pumped 45 sxs 60/40 pozmix - 4% gel with 100# hulls.  
Plugged tubing off.  
Pulled tubing out - 21 joints - plugged solid.  
Ran tubing to 2200'. Allied pumped 9 sxs gel spacer - followed with 45 sxs 60/40 pozmix - 4% gel.  
PTOH. Allied pumped 155 sxs cement with 300# hulls - circulated cement out 8 5/8".  
Shut in and pumped 90 sxs cement with 200# hulls down 4 1/2" casing.  
Max. P.S.I. 900#. S.I.P. 300#.  
Note: Pat Staab and Richard Williams witnessed the plugging of this well 50%/50%.

Perfs:

Top	Bot	Thru	Comments
3834	3838		

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 18 2009  
CONSERVATION DIVISION  
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #036226.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

FEB 12 2009

N-B CO., INC.

P.O. BOX 506

RUSSELL, KS. 67665

CONTR EMPHASIS OIL OPERATIONS

#4 BITTEL

CTY ELLIS

FIELD DIST 57 NORTH

21-12-20W  
NE NW NW

GEOL \_\_\_\_\_

ELV 2230 KB SPD 7/18/82 CARD ISSUED 9/30/82 IP P 25 BOPD & NW  
MARM 3834-3838

API 15-051-23,076

LOG	Tops	Depth Datum
HEEB	.....	3405-1175
TOR	.....	3514-1284
LANS	.....	3533-1303
BKC	.....	3788-1558
MARM	.....	3827-1597
ARB	.....	3908-1678
TD	.....	3930-1700

8 5 8 " 800 400SX. 4 1/2 " 3926 150SX

DST (1) 3724-80 TIMES NA. REC 10' M. W SO. SIP NOT  
AVAILABLE. FP 60-60#

MICT - CO. PF 16 3834-38. AC 250G. FRAC W 11.000#SD &  
NITROGEN. R&T. POP. P 25 BOPD (GR 38') 8 4 82

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS