

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23151-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 21-12S-20W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BITTEL Well #: 6
County: ELLIS Total Vertical Depth: 3914 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3910	0	w/125 sxs cmt
SURF	8.625	971	0	w/375 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/16/2009 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 335 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf Tech perfed at 2200' - 1625' - 775'.

Control # 20080062006

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2009 3:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3200'. Allied rigged to tubing - pumped 10 sxs gel - followed with 40 sxs 60/40 pozmix - 4% gel with 100# hulls mixed in.
Pulled tubing to 2200'. Allied rigged to tubing - pumped 120 sxs cement with 300# hulls mixed in to circulate cement to pit area.
Pulled tubing. Allied topped off 4 1/2" casing with 25 sxs cement.
Hole standing full.
Rigged to 8 5/8" casing - pumped 10 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3836	3845		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #39946.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

FEB 17 2009

PPT

N-B COMPANY, INC.

P.O. Box 506

#6 BITTEL

21-12-20W
SW NW NW

RUSSELL, KS 67665-0506

CONTR EMPHASIS OIL OPERATIONS

CTY ELLIS

GEOL

FIELD DIST 57 NORTH

ELV 2232 KB SPD 10/16/82


CARD ISSUED

1/6/83

IP P 30 BOPD & TR WTR

API 15-051-23,151

MARM 3836-3845



LOG	Tops	Depth Datum
TOP		3269-1037
HEEB		3497-1265
TOR		3521-1289
LANS		3537-1305
BKC		3784-1552
MARM		3829-1597
PENN CONG		3874-1642
TD		3914-1682

8 5/8 " 971-375SX, 4 1/2 " 3910/125SX
NO DST'S
MICT - CO. PF (MARM) 3836-45 W/4 SPF, AC 500G, SWB 12
BFPH, 85% OIL / 5 HRS. R&T, POP. P 30 BOPD & TR W. 11/4/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS