

6010179

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-195-21524-00-00

NW, SEC. 1, T 11 S, R 22 W/E  
2310 feet from N/S section line  
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Deutcher Well # A-1

Operator: Foxfire Exp.

County Trego

Name & Address 10403 W. Colfax Av. #210

Well Total Depth 3838 #124.74 feet

Lakewood Colo. 80215

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Foxfire Exp. License Number 6177

Address Same

Company to plug at: Hour: PM Day: 9 Month: 8 Year: 19 84

Plugging proposal received from Gary Fisher

(company name) Foxfire Exp. (phone) \_\_\_\_\_

were: order 210 sx. cement 50/50 portmix 6% Gal. 3% c.c.  
1.5x hulls 1.8 5/8 plug 1.5x Flow Seal.

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2151 Anhydrite 1630-70 Arbuckle - Yes.

Dakota. 1600 Plugging Proposal Received by Dale F. Batthazor. (TECHNICIAN)  
551. 850

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part (None)

Operations Completed: Hour: 11:PM Day: 9 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3800 for 30 mi.

25 SX. @ 3800

25 SX. @ 1650

100 SX. @ 850 mixed with 15x Flow Seal.

40 SX @ 320 dumped 15x hulls pushed plug to 40'

10 SX @ 40

Remarks: 105x in Rat Hole RECEIVED cementing on Sun.  
(If additional description use BACK of this form.)

INVOICED

DATE 8-28-84

INV. NO. 3339

SEP 11 1984

AGG 20 1984  
8-20-1984  
CONSERVATION DIVISION  
Wichita, Kansas

Dale F. Batthazor (TECHNICIAN)

SH  
8