

4-2

15-195-21368-00-00
4-061064

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-21,368
20' N. & 40' E. of
S2 SW / 4 SEC. 01, 11 S, 22 W
640 feet from S section line
3902 feet from E section line

Operator license# -

Lease Ronald Deutscher Well # 1

Operator: State of Kansas Fee Fund

County: Trego

Address: 2301 E. 13th Street - Dist.#4
Hays, Kansas 67601
Control #970165

Well total depth 3900 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: L&M Well Service, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 3:00 P.M. Day: 2 Month: April Year: 1997

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 400 sxs 60/40 posmix - 10% gel and hulls.
Plug with tubing.

RECEIVED
KANSAS CORP COM
4-10-1997
10 A 11:11

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30 P.M., Day: 2, Month: April, Year: 1997

Actual plugging report: 8 5/8" to 250' cwc. 5 1/2" to 3900'. Cleaned out bridges with tubing and power swivel. Perforated to 2175' - 1650' - 825'. Ran tubing to 2240' and pumped 80 sxs cement with 300# hulls. Pulled tubing to 1240' and circulated cement to surface with 100 sxs with 300# hulls. Pulled tubing and tied onto 5 1/2" casing pumped 95 sxs cement. Max. P.S.I. 1000#. S.I.P. 700#. Tied onto annulus and pumped 25 sxs. Max. P.S.I. 300#. S.I.P. 200#. Well appeared to have prior squeeze.

Remarks: Allied Cementing - Sally's Tank - L-K Wireline - J&T Consulting - R&S Roustabout.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2150 GL

I did[] / did not[] observe the plugging.

(agent)