

6 040356

15-195-21372-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SESENW, SEC. 5, T. 11 S, R. 22 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Operator: Mustang Dlg. Co.  
Name & Address: P.O. Box 1425  
H. Bend, Ks  
67530

Lease Name Faulkner Well # 1  
County Trego 128.38  
Well Total Depth 3950 feet  
Conductor Pipe: Size - feet -  
Surface Casing: Size 8 5/8 feet 214 w/150

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing & Son Cmtg License Number \_\_\_\_\_

Address Chase, Ks - Hays, Ks

Company to plug at: Hour: 9:00 AM Day: 17 Month: 4 Year: 19 85

Plugging proposal received from Ralph Glass

(company name) Kelso Csg (phone) \_\_\_\_\_

were: 5 1/2" set @ 3735 w/175 sv P.B @ 3695'

T.O.C. 2820' Top perf 3579 P.B. 5 sv cmt - sand

to 3525' -> 5 sv cmt. Rec. 2800' of 5 1/2" csg.

Ordered 200 sv 6 3/4 poz, 8% gel; 30 sv gel; 8 sv hulls;

+ 8 3/4 w. plug.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 AM Day: 17 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT

Impd in 3 sv hulls -> 50 sv cmt w/ 1 sv hulla ->

15 sv gel w/ 1 sv hulla -> 100 sv cmt w/ 2 sv hulla ->

15 sv gel w/ 1 sv hulla -> Rel plug -> 50 sv cmt.

M.A.X. 800 # P.S.T Shut-in 300 # P.S.T.

RECEIVED  
STATE CORPORATION COMMISSION  
5-10-1985  
MAY 10 1985

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

Signed Dennis L. Hamel  
(TECHNICIAN) 5-10-85

INDEXED  
DATE 5-14-85  
IN. NO. 8132