

3021628

TO:

KCCPCT per
UIC.

API NUMBER 15- 001-23,678 -00-02

STATE CORPORATION COMMISSION

NE nesw NE, SEC. 19, T 26 S, R 19 E

CONSERVATION DIVISION - PLUGGING SECTION

3465 3795 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1815 1485 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DIETRICH WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 5963

WELL TOTAL DEPTH 918 FEET

OPERATOR: WILLIS ENERGY

PRODUCTION CSG: SIZE FEET

NAME AND ROUTE 2, BOX 255

SURFACE CASING: SIZE 7" FEET 20'

ADDRESS NEODESHA, KS 66757

ABANDONED OIL WELL GAS WELL INPUT WELL E-24-397 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR FULLER OIL CO. TOOLS

LICENSE NUMBER 31094 99998

ADDRESS 1312 E. CARPENTER, IOLA, KS 66749

COMPANY TO PLUG AT: HOUR: 10:00AM DAY: 8 MONTH: 4 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM TAB SWITZER

(COMPANY NAME) WILLIS ENERGY (PHONE) 316-325-5189

WERE: THIS WELL CONSISTED OF 2 7/8" CASING TO 914' THAT HAD BEEN CEMENTED IN FROM
 BOTTOM TO TOP. THE 2 7/8" HAD BEEN PERFORATED FROM 850' TO 859'. THE PLUGGING
 PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 8 MONTH: 4 YEAR: 99

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 850'. CEMENT WAS
 PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE.

THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 16 SACKS
 OF CEMENT WERE PUMPED INTO THIS WELL.

KANSAS CORPORATION COMMISSION

FEB 25 2009

RECEIVED

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

PRX