

State of Kansas



15-051-22764-00-00

FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Allan Miller of Pioneer Drilling Co. has this
date requested permission to plug the following described well:

Operator's Full Name: Okmar Oil Co.

Complete Address: 970 Fourth Financial Center, Wichita, Ks. 67202

Lease Name: Hall Well No. 2

Location: NE SE SW Sec. 35 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated:

Mr. Allan Miller was instructed to plug the well as follows:

8 5/8" 290' S.P. cuc. W/ 160 sacks common 2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' W/ 70 sacks cement

2nd plug @ 270' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' with 10 sacks cement

Circulate 10 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
1-25-1982
JAN 25 1982
CONSERVATION DIVISION
Wichita Kansas

Very truly yours,

[Signature]
Conservation Division Agent