



15-051-20668-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10-5-1970
OCT 5 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg. has this
date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Leben Et al

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: Metz Well No. 1

Location: NW NE NW Sec. 24 Twp. 11 Rge. (E)(W) 19

County: Ellis Total Depth 3488 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gustus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Massie
Conservation Division Agent