



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of Dreiling Drlg. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Co.

Complete Address: 605 Sutton Place Wichita, Ks.

Lease Name: Armbrister Well No. 1

Location: SE NW SW Sec. 1 Twp. 11 Rge. 20 (E)(W) XX

County: Ellis Total Depth 3721 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace 70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Red Massey
Conservation Division Agent