

State of Kansas



FORM CP-2

15-051-22760-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Everett Michelson of Dreiling Oil, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Triple "H" Oil Operations

Complete Address: 1011 Military Road, Hays, Kansas 67601

Lease Name: Beath Well No. #1

Location: NW NW NW Sec. 4 Twp. 11 Rge. 20 (E) (W)

County: Ellis Total Depth: 3695'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A  X

Other well as hereafter indicated: \_\_\_\_\_

Mr. Everett Michelson was instructed to plug the well as follows:

8 5/8"-263' s. p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 840' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole and 5 sacks in mouse hole.

Very truly yours,

  
Conservation Division Agent

RECEIVED  
CONSERVATION DIVISION  
12-21-1981  
DEC 21 1981