

State of Kansas



FORM CP-2

15-051-22605-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Wilmer Dreiling of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: K & E Petroleum, Inc.

Complete Address: 100 S. Main, Suite #300, Wichita, Ks. 67202

Lease Name: Fischer Well No. #1

Location: 120' No. of Center-SW-NW Sec. 9 Twp. 11 Rge. 20 (E) (W)

County: Ellis Total Depth: 3624'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Wilmer Dreiling was instructed to plug the well as follows:

13 3/8" Conductor String-58' w/ 60 sacks common-2% Gel.-3% Cal. Cl.

8 5/8"-321' sp. cuc. w/ 185 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem w/heavy mud between all plugs.

1st plug @ 840' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

Very truly yours,

STATE CORPORATION COMMISSION

CONSERVATION DIVISION

Wichita, Kansas

10-19-1981

CONSERVATION DIVISION

Wichita, Kansas

[Signature]
Conservation Division Agent