



15-051-20539-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agents)

RECEIVED
STATE CORPORATION COMMISSION
12-1-1969
DEC 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Imperial Drlg. has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Burton W. Schmidt

Complete Address: 208 Brown Bldg., Wichita, Ks.

Lease Name: Fischer Well No. 1

Location: SE SE SE Sec. 9 Twp. 11 Rge. (E)(W) 20

County: Ellis Total Depth 3686' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circu;ate heavy mud, set cementing plug at 500' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red F. Muesel
Conservation Division Agent