

15-051-00950-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 1 Twp. 11S Rge. 20 (X) (W)

Location as "NE/CNW/SW" or footage from lines. NW SW SE

Lease Owner Petroleum Management Corp.

Lease Name Armbruster Well No. 1

Office Address Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 8/9/56 19

Application for plugging filed 8/8/56 19

Application for plugging approved 8/8/56 19


Plugging commenced 8/8/56 19

Plugging completed 8/8/56 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3742 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	204'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

**Filled with heavy mud from 3742 up to 200'. Set wood plug @ 200' using 1/2 sack hulls and 20 sacks cement thru drill pipe up to 170'. Filled with heavy mud from 170' up to 40'. Set wood plug @ 40' with 1/2 sack hulls and 10 sacks cement to cellar 0
Completed at 5:30 p.m. 8/8/56**

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. C. T. Honaker

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 56

My commission expires 1-30-57.

Margie Cooper
Notary Public.

PLUGGING
FILE SEC. 1 T. 11 R. 20W
BOOK PAGE 89 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
8-13-1956
AUG 13 1956
CONSERVATION DIVISION
Wichita, Kansas

15-051-00950-0-0-00

Petroleum Management Corp.
Armbruster #1

NW SW SE 1-11S-20W
Ellis County, Kansas

Sierra Petroleum Co., Inc. - Contr.

Total Depth: 3742*

Elev: 2142 DF

Comm: 7/27/56

Comp: 8/9/56

Casings:

Cement

8 5/8 @ 204*

w/125 sks Cement 2% Gel 3% CC

DEPTH	FORMATION
Surface clay & rock	40
Shale & sand	125
Shale & shells	350
Sand & shale	547
Shale	690
Sand & shale	810
Shale, shells & sand	1090
Sand	1250
Red Bed	1545
Anhydrite	1585
Shale & shells	1900
Salt, shale & shells	2000
Shale & Lime	2980
Lime	3063
Lime & shale	3299
Lime	3349
Lime & shale	3425
Lime	3676
Conglomerate	3730
Arbuckle	3742

Tops:	FORMATION	DEPTH
Anhydrite		1545
Heebner		3378
Kansas City		3435
Arbuckle		3730
Total Depth		3742

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 10th day of August, 1956.

Margie Cooper
Notary Public

My commission expires: 1-30-57.

STATE COMMISSION COMMISSIONER
8-13-1956
NOTARY PUBLIC

PLUGGING
FILE SEC. 1 T. 11 R. 20W
BOOK PAGE 89 LINE 31

CONSERVATION DIVISION
Wichita, Kansas