


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 1 Twp. 11S Rge. (E) 20 (W)  
Location as "NE/CNW%SW%" or footage from lines CWL SW SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name J. HUCK Well No. 1  
Office Address Box 797 - Gt. Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10/31 1963  
Application for plugging filed 10/31 1963  
Application for plugging approved 10/31 1963  
Plugging commenced 10/31 1963  
Plugging completed 10/31 1963  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan - Russell, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3693 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	214	8-5/8"	214	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1/3 sack hulls and wooden plug set @ 200'  
Mixed 25 sacks cement through drill pipe  
1/3 sack hulls and wooden plug set @ 40'  
Mixed 10 sacks cement through drill pipe

STATE OF KANSAS  
NOV 4 1963  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Box 797 - Gt. Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
Box 797 - Gt. Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of November, 1963

My commission expires Jan. 26, 1967  
Carmen R. Cook Notary Public.

INVOICED  
DATE 11/4/63  
INV. NO. 8026-W

15-051-03760-00-00

WELL LOG

Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas

J. HUCK #1  
CWL SW SW Sec. 1-11S-20W  
Ellis County, Kansas

Commenced: 10-23-63  
Completed: 10-31-63

D & A

Contractor: Chief Drilling Co., Inc.

Casing Record: 8-5/8" set @ 214' w/160 sacks Sunset Cement.

11-4-1963

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	214	2091 Gr.
Shale & Sand	214	1000	2093 D.F.
Shale & Sand streaks Shells	1000	1487	2096 K.B.
Anhydrite	1487	1525	
Shale & Shells	1525	1930	<u>FORMATION TOPS</u>
Shale & Lime	1930	3109	Anhydrite 1487 + 609
Lime	3109	3323	Topoka 3109 -1013
Shale & Lime	3323	3359	Heebner 3323 -1227
Lime	3359	3577	Toronto 3346 -1250
Lime & Shale	3577	3630	Lansing 3359 -1263
Conglomerate	3630	3686	Base Kansas City 3577 -1481
Dolomite	3686	3693	Conglomerate 3630 -1534
Total Depth	3693		Arbuckle 3686 -1590
			Total Depth 3693 -1597

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the CWL SW SW Sec. 1-11S-20W, Ellis County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 1st day of November, 1963.

*Carmen R. Cook*  
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.