


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-21809-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202


Ellis County. Sec. 4 Twp. 11S Rge. 20 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C W/2 SE NW
Lease Owner Liberty Enterprises, Inc.
Lease Name Veatch Well No. #1
Office Address 308 West Mill Plainville, Ks. 67663
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed February 4, 1980
Application for plugging filed February 4, 1980
Application for plugging approved February 4, 1980
Plugging commenced February 4, 7:00 A.M. 1980
Plugging completed February 4, 8:45 A.M. 1980
Reason for abandonment of well or producing formation
No Commercial Production
If a producing well is abandoned, date of last production
19



Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Marvin Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface casing	common	0	212.92'	8 5/8"	212.92'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plug #1 @ 775' with 70 sxs
Plug #2 @ 200' with 20 sxs
Plug #3 @ 40' with 1 sx Hulls, wooden plug & 10 sxs
5 sxs in Rathole
Total 105 sxs 50-50 poz 6% gel




(If additional description is necessary, use BACK of this report)
Name of Plugging Contractor Pioneer Drilling Company, Inc.
308 West Mill Plainville, Kansas 67662

STATE OF Kansas COUNTY OF Rooks, ss.
Roger L. Comeau (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roger L. Comeau
308 West Mill Plainville, Kansas 67662
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1980
Connie Jo Austin
Notary Public.

My commission expires _____



WELL LOG

OPERATOR: Liberty Enterprises, Inc.

WELL NAME: Veatch #1 LOCATION: C W/2 SE NW 4-11S-20W

COUNTY: Ellis STATE: Kansas

WELL COMMENCED: January 25, 1980 WELL COMPLETED: February 4, 1980

ELEVATION: 2096' K.B. TOTAL DEPTH: 3703'

PRODUCTION: Dry Hole RIG NO: #1

CASING - 8-5/8": 212.92' of 28# cement with 135 sxs common 2% gel 3% cc
 5-1/2": none

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	220'		220' - 3/4 degree	
220'	585'	sand and shale		
585'	1444'	sand and shale		
1444'	1522'	shale and sand		
1522'	1586'	Anhydrite	1547' - 3/4 degree	
1586'	1997'	shale		
1997'	2230'	shale		
2230'	2346'	shale	2245' - 1 degree	
2346'	2493'	limes and shale		
2493'	2676'	lime and shale		
2676'	2840'	shales and shells		
2840'	3031'	shales and shells		
3031'	3130'	lime and shale		
3130'	3169'	lime and shale		
3169'	3310'	lime and shale		
3310'	3376'	lime and shale		
3376'	3449'	lime		
3449'	3502'	lime and shale		
3502'	3533'	lime and shale		
3533'	3533'			
3533'	3555'	lime and shale		
3555'	3605'	lime and shale		
3605'	3660'	lime		
3660'	3703'	shale		
3703'	3703'			
3703'	RTD			

RECEIVED
 STATE CORPORATION COMMISSION
 2-15-1980
 FEB 15 1980
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS
 COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Regan L. Corne

SUBSCRIBED AND SWORN TO, BEFORE ME, This 14th day of Feb., 1980.

Connie Jo Austin
 -NOTARY PUBLIC

