


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-21642-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 4 Twp. 11S Rge. 20W ~~E&W~~
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
C E/2 SE NW
Lease Owner Icer Addis
Lease Name Veatch Well No. 1
Office Address 5307 E. Central, Wichita, KS 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above Section Plat

Date Well completed March 12 1979
Application for plugging filed March 12 1979
Application for plugging approved March 12 1979
Plugging commenced March 12 1979
Plugging completed March 12 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar, Palco
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3725
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well plugged as follows:

Filled hole w/mud; spot 70 sx @ 600'; mud to 200'; spot 20 sx mud to 40'; 1/2 sx hulls and wood plug for solid bridge; 10 sx to base of cellar; 5 sx in rat hole; complete @ 1 a.m. 3-12-79 by Sun (used 50/50 pozmix w/6% gel)

Witnessed: Gilbert Balthazar - St. Plugger - Palco
Gary Bagby - Sterling, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-14-1979
MAR 14 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


HUSKY DRILLING CO., INC.

800 Biting Building, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1979

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





15-051-21642-00-00

800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

WELL LOG- - - - -Veatch No. 1
Location: C E/2 SE NW of Sec. 4-11S-20W, Ellis Co., Kansas

OWNER: Icer Addis
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: March 5, 1979
COMPLETED: March 12, 1979

Rotary Total Depth: 3725

<u>LOG</u>	<u>CASING</u>
0 - 229 Soil & sand	Ran 6 jts., 8-5/8" @ 20#, 8V, Rge 3 used csg., tallied @ 222.19'; set @ 226' KB w/150 sx 60/40 pozmix 2% gel 3% cc - circulated - plug down @ 3 p.m. by Sun 3-6-79.
229 - 690 Shale, blue & gray	
690 - 860 D. sand	
860 - 1030 Shale & Sand	
1030 - 1280 C.H. Sand	
1280 - 1515 Red bed & shale	
1515 - 1555 Shale	
1555 - 1604 Anhydrite	
1604 - 2185 Shale & Shells	
2185 - 3348 Shale & Lime	
3348 - 3540 Lime	
3540 - 3647 Lime & Shale	
3647 - 3720 Lime	
3720 - 3725 Dolomite	Plugged 3-12-79 @ 1 a.m. 3-12-79 by Sun

RECEIVED
STATE CORPORATION COMMISSION
3-14-1979
MAR 14 1979

CONSERVATION DIVISION
Wichita, Kansas