

15-051-19219-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County, Sec. 4 Twp. 11 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner C-G Drilling Co. & Holly Oil Company

Lease Name Keller "B" Well No. 1

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-28 19 54

Application for plugging filed 11-28 19 54

Application for plugging approved 11-28 19 54

Plugging commenced 11-28 19 54

Plugging completed 11-28 19 54

Reason for abandonment of well or producing formation Lost drill pipe in hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3278 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	175'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 170'; set plug;
1/2 sack hulls, 15 sacks cement. Filled
hole with mud to 40' set plug then filled
to top with 10 sacks cement, 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Vicky Jacobs (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Vicky Jacobs Office Manager
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 1954

Barbara Donaldson
Notary Public.

My commission expires June 17, 1957

12-4-1954



15-051-19219-00-00
CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. & Holly Oil Co. FARM NAME Keller "B" #1
 LOCATION NW NW SW, Sec. 4-11-20W
 POOL NAME Wildcat COUNTY Ellis STATE Kansas
 COMMENCEMENT DATE November 20, 1954 COMPLETION DATE November 28, 1954

LOG OF WELL

Elevation:
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	175	Shale-Shells-Sand		
175	1100	Shale-Shells-Sand		
1100	1510	Shale-Shells-Red Bed-Sand	0° - 1500'	
1510	1550	Anhydrite		
1550	1775	Shale-Lime		
1775	2060	Lime-Shale	0° - 2000'	
2060	2260	Lime-Shale		
2260	2385	Lime-Shale		
2385	2520	Lime-Shale	0° - 2500'	
2520	2740	Lime-Shale		
2740	2865	Lime-Shale		
2865	3025	Lime-Shale	0° - 3000'	
3025	3235	Lime-Shale		
3235	3278	Lime-Shale		Fishing

CASING LEFT IN HOLE AFTER COMPLETION

Ran 174.85' of 8-5/8" Surface Casing.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs
 Office Manager

Subscribed and sworn to before me this 3rd day of December, 1954.

My commission expires:
 June 17, 1957

Barbara Donaldson
 Notary Public

4 11 2010
 81 19

12-4-1954