

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH

	o		

Locate well correctly on above
Section Plat

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines... NW NE NW
Lease Owner... **Sohio Petroleum Company**
Lease Name... **Veatch** Well No. **1**
Office Address... **Russell, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed... **January 17 1948**
Application for plugging filed... **January 17 1948**
Application for plugging approved... **January 17 1948**
Plugging commenced... **January 17 1948**
Plugging completed... **January 17 1948**
Reason for abandonment of well or producing formation... **Dry Hole**

If a producing well is abandoned, date of last production... **Dry Hole 19**
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? **Yes, from Mr. C. D. Stough by telephone**
Mr. C. D. Stough

Name of Conservation Agent who supervised plugging of this well...
Producing formation... **None** Depth to top... Bottom... Total Depth of Well **3844** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
No commercial oil nor gas shows from top to bottom				13 3/8"	233'	None. Cemented to top.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

3844' to 220' - Heavy Mud
220' to 200' - Cement - 20 Sacks
200' to 14' - Heavy Mud
14' to 4' - Cement - 10 Sacks
4' to 0 - Clay

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to... **Sohio Petroleum Company**
Address... **Box 671, Russell, Kansas** 1-27-1948

STATE OF **Kansas**, COUNTY OF **Russell**, ss.

Doyle Fair (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Doyle Fair*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this **26th** day of **January**, 19 **48**

My commission expires May 8, 1948.
My commission expires...
Bernie J. Smith Notary Public.

PLUGGING
FILE SEC **4** T **11** R **20W**
BOOK PAGE **11** LINE **4**

15-051-19218-00-00
CONTRACTOR'S VERIFIED LOG

Operator **Sohio Petroleum Company** Farm Name **Veatch** Well No. **1**

Location **NW NE NW Section 4-11S-20W**

Pool Name **Marcotte** County **Ellis** State **Kansas**

Commencement Date **January 3, 1948** Completion Date **January 17, 1948**

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	5	Rig		
5	10	Cellar		
10	20	Shale		
20	45	Lime		
45	155	Shale		
155	175	Sand		
175	630	Shale	Syfo at	
630	665	Sand	500'	
665	760	Shale		
760	850	Sand		
850	1050	Shale	Syfo at	
1050	1085	Sand	1000'	
1085	1345	Shale and Sand		
1345	1500	Shale and Shells	Syfo at	
1500	1595	Red Bed	1500'	
1595	1630	Anhydrite		
1630	1985	Shale and Shells		
1985	2120	Salt and Shale	Syfo at	
2120	2340	Shale and Shells	2000'	
2340	2400	Brk. Lime		
2400	2470	Shale and Lime		
2470	3347	Broken Lime	Syfo at	
3347	3649	Lime	2500'	
3649	3715	Shale and Lime Shells	Syfo at	
3715	3799	Conglomerate	3000'	
3799	3844	Arbuckle Lime		
			ALL OK	

PLUGGING
 FILE 4 11 20W
 11 4