

15-051-22605-00-00

300

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 9 TWP. 11S RGE. 20W E/W  
Location as in quarters or footage from lines:  
100' N of C SW NW NW


Lease Owner K & E Petro., Inc.  
 Lease Name FISCHER Well No. 1  
 Office Address 300 Hardage Center, 100 S. Main, Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 10/12/81  
 Application for plugging filed 10/12/81  
 Plugging commenced 10/12/81  
 Plugging completed 10/12/81  
 Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? YES

Locate Well  
correctly on above  
Section Platt.

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3624'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 840' with 70 sx.  
Set 2nd plug @ 300' with 40 sx.  
Set 3rd plug @ 40' Solid Bridge with 10 sx.  
5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.  
Plug was down @ 8:15 a.m., 10/12/81.

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-22-1981  
 CONSERVATION DIVISION  
 Wichita Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry  
 Elizabeth G. Terry Notary Public  
 NOTARY PUBLIC  
 STATE OF KANSAS

500

15-051-22605-00-00

CONTRACTORS WELL LOG

OPERATOR: K & E Petroleum, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: FISCHER #1  
 LOCATION: 100' N of C SW NW NW, Sec. 9-11S-20W  
 Ellis County, Kansas  
 SPUD DATE: 10/02/81  
 COMPLETION DATE: 10/12/81

0	60	Clay, Sand & Shale
60	325	Sand & Shale
325	701	Shale & Sand
701	1351	Sand & Shale
1351	3200	Shale
3200	3425	Shale & Lime
3425	3615	Lime
3615	3624	Dolomite
	3624	Rotary Total Depth

Spud hole @ 10:30 p.m., 10/02/81. Drilled 60' of a 12 1/4" hole. Ran 2 jts. of 13 3/8 56# conductor string. Set @ 55' and cemented with 60 sx. Common 2% gel, 3% c.c. Plug was down @ 1:45 a.m., 10/03/81. Cement did not circulate.

3624' TD. Set 1st plug @ 840' with 70 sx. Set 2nd plug @ 300' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c. State plugger Gilbert Scheck. Plug was down @ 8:15 a.m., 10/12/81.

SAMPLE TOPS:

Anhydrite 1442'  
 B/Anhydrite 1493'

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-22-1981

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the FISCHER #1, 100' N of C SW NW NW, Sec. 9-11S-20W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 20th day of October, 1981.

Elizabeth G. Terry  
 Elizabeth G. Terry  
 NOTARY PUBLIC

my commission expires 7-13-85

