

15-051-24634-00-00  
WELL PLUGGING RECORD  
K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER 15-051-24,634

LEASE NAME Fischer

WELL NUMBER 1

4220 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 9 TWP. 11S RGE. 20 ~~XXXX~~(W)

COUNTY Ellis

Date Well Completed 02-26-90

Plugging Commenced 02-26-90

Plugging Completed 02-26-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Osborn Heirs Co.

ADDRESS P. O. Box 17968, San Antonio, TX 78268

PHONE#(512) 826-0700 OPERATORS LICENSE NO. 5249

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02-26-90 (date)

by State Pluggger, Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3699'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	213.94'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud in hole. 1st plug from 3699' to 3599' w/25 sc. 2nd plug from 1475' to 1375' w/25 sx. 3rd plug from 680' to 280' w/100 sc. and 1 sk. Cello Flake. 4th plug rom 250' to 170' w/20 sx. 5th plug from 40' to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie DRilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Osborn Heirs Co.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

MAR 19 1990  
3-19-1990

CONSERVATION DIVISION  
SUBSCRIBED AND SWORN TO before me this 16th day of March, 1990

Sharan J. Branstetter  
Notary Public

My Commission Expires: May 18, 1993

