

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,818-00-00

LEASE NAME Mixer

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

500 Ft. from N Section Line

1440 Ft. from W Section Line

LEASE OPERATOR Hess Oil Company

SEC. 13 TWP. 11 RGE. 20 (E or W)

ADDRESS P.O. Box 1009, McPherson, KS 67460

COUNTY Ellis

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Date Well Completed 8/14/93

Character of Well D & A

Plugging Commenced 8/14/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/14/93

The plugging proposal was approved on 8/2/93 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation Kansas City Depth to Top 3297 Ft. Bottom P.B.T.D. 3340 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Conductor		39'	0'	13-3/8"	39'	None
Surface		209'	0'	8-5/8"	209'	None
Production		3497'	0'	5-1/2"	3497'	2195'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Wireline bridge plug @ 3340'. Sanded to 3280' and spotted 5 sacks cement. Pulled 2195' of 5-1/2" casing, & cementing on way out as follows: 35 sacks @ 2140', 25 sacks @ 1425', 65 sacks & 100# hulls @ 700', 40 sacks @ 250' to surface, and 10 sacks top cap. 175 sacks total - 60/40 Pozmix, 1/4# flooseal per sack.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hess Oil Company License No. RECEIVED

Address P.O. Box 1009, McPherson, KS 67460 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company 8-18-1993
AUG 18 1993

STATE OF KANSAS COUNTY OF MCPHERSON, ss. CONSERVATION DIVISION
Wichita, Kansas

James H. Hess (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James H. Hess

(Address) Same

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1993

Bryan K. Hess
Notary Public

My Commission Expires:

